

AD-A156 419


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
MILTON THREE PONDS DA. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78

1/1

UNCLASSIFIED

F/G 13/13

NL



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 419

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00320	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Milton Three Ponds Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE August Dam
		13. NUMBER OF PAGES 52
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Piscataqua River Basin Milton, New Hampshire Salmon Falls River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is 19 ft high and 156 ft. long. It is a gravity dam consisting of a dry stone masonry bed over which a reinforced concrete superstructure has been built. The dam is in good condition. There are a few minor concerns which should be corrected. Based on size and hazard classifications in accordance with Corps guidelines the test flood is the PMF. A major breach at top of dam would probably result in the loss of less than a few lives and appreciable property damage.		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:

NEDED

Honorable Meldrim Thomson, Jr.
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	23

Dear Governor Thomson:


I am forwarding to you a copy of the Milton Three Ponds Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, The New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely yours,


JOHN P. CHANDLER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated



MILTON THREE PONDS DAM

NH 00320

PISCATAQUA RIVER BASIN
MILTON, NEW HAMPSHIRE

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: NH00320
Name of Dam: Milton Three Ponds Dam
Town: Milton
County and State: Strafford County, New Hampshire
Stream: Salmon Falls River
Date of Inspection: 19 June 1978

BRIEF ASSESSMENT

Milton Three Ponds Dam is 19 feet high, is 16½ feet wide, and is 156 feet long. It is a gravity dam, consisting of a dry stone masonry bed over which a reinforced concrete superstructure has been built. The dam spans a middle reach of the Salmon Falls River, and is located in east central New Hampshire. It has two low-level outlet gates; the spillway extends across the length of the dam with 25 bays of stoplogs. Maximum storage capacity is about 15,000 acre-feet. Milton Three Ponds Dam is used for industrial process water as well as for recreational purposes. The pond is about 5 miles in length with a surface area of about 900 acres.

The dam is in good condition. Minor concerns are: the displacement of a few large stones from the downstream face; structural deterioration of the concrete, including cracking, spalling, and erosion that has exposed reinforcing bars; and a minor seepage at the toe of the dam at the west abutment.

Based on size and hazard classifications in accordance with Corps guidelines, the test flood is the Probable Maximum Flood. With stoplogs in place a PMF outflow of 35,000 cfs (324 csm) would overtop the dam by 12.8 feet; therefore the spillway is considered inadequate. With stoplogs, the spillway will pass 1300 cfs or 4 percent of the PMF. With stoplogs removed, the spillway will pass 23,700 cfs. A major breach at maximum pool would probably result in the loss of less than 10 lives and appreciable property damage.

The owner, New Hampshire Water Resources Board, should implement the results of the recommendations given in Section 7.2. within 3 years after receipt of this Phase I inspection report. The operating and maintenance measures recommended in Subsection 7.3.b. should be implemented within one year after receipt of this Phase I inspection report.

Warren A. Guinan

Warren A. Guinan
Project Manager
N.H. P.E. 2339

This Phase I Inspection Report on Milton Three Ponds Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman
Chief, Foundation and Materials Branch
Engineering Division




FRED J. RAVENS, Jr., Member
Chief, Design Branch
Engineering Division



SAUL COOPER, Member
Chief, Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers (OCE), Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

CONTENTS

Title	Page
LETTER OF TRANSMITTAL.....	i
BRIEF ASSESSMENT.....	ii
REVIEW BOARD PAGE.....	iii
PREFACE.....	iv
CONTENTS.....	v
OVERVIEW PHOTO.....	vi
LOCATION MAP.....	vii

REPORT

SECTION

1	PROJECT INFORMATION.....	1
	1.1 General.....	1
	1.2 Description of Project.....	1
	1.3 Pertinent Data.....	4
2	ENGINEERING DATA.....	7
	2.1 Design.....	7
	2.2 Construction.....	7
	2.3 Operation.....	7
	2.4 Evaluation.....	7
3	VISUAL INSPECTION.....	8
	3.1 Findings.....	8
	3.2 Evaluation.....	10
4	OPERATIONAL PROCEDURES.....	11
	4.1 Procedures.....	11
	4.2 Maintenance of Dam.....	11
	4.3 Maintenance of Operating Facilities.....	11
	4.4 Description of Any Warning System in Effect....	11
	4.5 Evaluation.....	11
5	HYDROLOGY AND HYDRAULIC ANALYSIS.....	12
	5.1 Evaluation of Features.....	12
6	STRUCTURAL STABILITY.....	14
	6.1 Evaluation of Structural Stability.....	14
7	ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES.....	16
	7.1 Dam Assessment.....	16
	7.2 Recommendations.....	17
	7.3 Remedial Measures.....	17

APPENDICES

	Designation
CHECK LIST - VISUAL INSPECTION.....	A
INSPECTION REPORTS/SKETCHES.....	B
PHOTOGRAPHS (Figures 2 - 16).....	C
HYDROLOGY/HYDRAULICS.....	D
INVENTORY DATA.....	E



Figure 1 - Overview of Milton Three Ponds Dam.

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
MILTON THREE PONDS DAM

SECTION I
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols & Company, Inc. under a letter of May 3, 1978 from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0329 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify, and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Milton Three Ponds Dam occupies an area on the Maine-New Hampshire state line, bordering the Towns of Milton, New Hampshire and Lebanon, Maine. The lake is formed by the confluence of the Branch and Salmon Falls Rivers, and consists of Milton, Town House, and Northeast Ponds. The Salmon Falls River joins the Cocheco River about 25 miles below the dam to form the Piscataqua River. The dam itself is located in Milton, New Hampshire, shown on the U.S.G.S. Quadrangle, Berwick, Maine-New Hampshire, with coordinates approximately at N 43° 24' 56", 70° 59' 08",

Strafford County, New Hampshire. (See Location Map page vii.)

b. Description of Dam and Appurtenances. Milton Three Ponds Dam, as it exists today, is a gravity dam consisting of a dry stone masonry base over which a reinforced concrete superstructure has been built. The dam is 19 feet high, 16½ feet wide, and 156 feet long. The concrete superstructure consists of seven sections of stoplogs, a low-level gated outlet structure, and a reinforced concrete foot bridge. The seven sections of stoplogs are divided as follows: Five sections of four bays each are located to the left (east) of the gate structure, a section of three bays of stoplogs occupies a space vertically above the two-compartmented gated low-level outlet, and a section of two bays right (west) of the gate structure. A wooden gatehouse has been constructed above the three-bay spillway and contains the gate hoisting mechanisms. Two wooden gates, 27" H x 44" W, each fitted with two timber stems with rack and pinion mechanisms are electrically operated by a single motor with a transfer belt drive.

c. Size Classification. Intermediate (Hydraulic height - 18 feet; Storage - 15,000 acre-feet) based on storage (≥ 1000 to $< 50,000$ acre-feet) as given in OCE Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Significant hazard. A major breach at maximum pool would probably result in the loss of less than 10 lives and appreciable property damage.

e. Ownership. The Great Falls Manufacturing Company purchased the original dam and privilege in 1824. Ownership of Milton Three Ponds Dam passed on to the Public Service Company of New Hampshire sometime between 1922 and 1929. The New Hampshire Water Resources Board (NHWRB) acquired the dam and water rights in December of 1963.

f. Operator. Mr. Vernon K. Knowlton, Chief Engineer, New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301, is responsible for the operation of Milton Three Ponds Dam. Phone is (603) 271-3406.

g. Purpose of Dam. The original structure impounding Milton Three Ponds Dam was constructed to provide greater industrial water storage for downstream mills. Under the ownership of the Public Service Company of New Hampshire, Milton Three Ponds Dam was utilized mainly as conservation storage for the generation of hydro-electricity for the region, with some recreational usage. Today, Milton Three Ponds Dam is used primarily for recreation, while also providing water storage for downstream industries.

h. Design and Construction History. Little information was disclosed concerning the original (circa 1824) design and construction of the dam. The dam is reported to have been modified 6 times in the next 91 years as follows: The dam was raised 4 feet in 1835 (called 9 feet high), raised 6 more feet in 1835 and this 6 feet was removed in 1847. The latter 6 feet was reconstructed again at some unknown later date. The dam was raised 2 feet more in 1872 (then called 16 feet); the cement facing and gateways were built in 1915. (See Public Service Company of New Hampshire letter of 9/29/1949, Appendix B.)

In 1924, in correspondence to the New Hampshire Public Service Commission, I.W. Jones & Co., Engineers, reported "...the outlet of Milton Three Ponds. It is about 16 ft. in height by 136 ft. in length. It is composed of wooden bents set about 6 ft. on centers with a walk across the top from which 7 ft. of flashboards can be drawn. It is founded on a rough stone wall, the upstream side of which is faced with concrete. This dam was built in 1873 and the wooden sheet piling originally placed at the upstream side was substituted by concrete about eight years ago. Plans have already been made for replacing the wooden bents with reinforced concrete." (See Appendix B.)

The present outlet facilities at Milton Three Ponds were constructed in 1968 by the NHWRB.

i. Normal Operational Procedures. No formal operational and maintenance procedures were disclosed. Normal pool elevation during the summer months is 413.8 feet MSL. This level is maintained by keeping one of the two waste gates open 3½ inches, supplying a minimum flow of 20-30 cfs for downstream users, and setting the stoplogs at 15.2 feet on the gage (413.8 feet MSL) upstream of the dam. After the recreational season the impoundment is drawn down approximately 6 feet, to 9.0 feet on the gage (407.6 feet MSL) by removing stoplogs. The dam is visited on a weekly basis by the NHWRB. Telecommunication with the dam on a daily basis provides the NHWRB with information on discharge and lake level.

j. Regulating Outlets. The two reinforced concrete low-level outlets have downstream portal openings of about 5' x 5' separated by a 30" wide central pier. The gates are wooden, each is 27" H x 44" W, and they are fitted with two timber lifting stems. The gates can be raised 27 inches.

1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 108 square miles (69,120 acres) of primarily wooded terrain with some urbanized area. The normal recreation level has a surface area of 900 acres, which is equivalent to 1 percent of the watershed.

b. Discharge at Damsite

(1) Outlet Works (conduits) - Two 27" x 44" @ Invert Elevation 400.0 ft. \pm MSL. Total capacity - 380 cfs @ 413.8' MSL.

(2) The maximum known flood discharge at the damsite is unknown. However, there was a gaging station on the Salmon Falls River at South Lebanon, Maine (D.A. 137 sq. mi.), and the March 1939 flood produced a peak flow of 5490 cfs.

(3) Stoplog spillway capacity at recreational pool elevation (stoplogs in place) - 0 cfs @ 413.8' MSL.

(4) Stoplog spillway capacity at maximum pool elevation - (stoplogs in place) - 1300 cfs @ 416.2' MSL.

(5) Total project discharge at Test Flood elevation (stoplogs in place) - 35,000 cfs @ 429.0' MSL.

c. Elevation (ft. above MSL)

(1) Top of dam - the crest varies from 416.2 to 417.6

(2) Test Flood pool - 429.0

(3) Design surcharge - original design - unknown

(4) Full flood control pool - not applicable

(5) Recreation pool - 413.8

(6) Top of stoplogs - 413.8

(7) Spillway crest - 408.3 (assuming stoplogs removed)

(8) Upstream portal invert low-level conduit - 400.0

(9) Streambed at centerline of main dam - 398.6
(downstream invert of stilling basin measured 8/2/78)

(10) Maximum tailwater - unknown

d. Reservoir (miles)

- (1) Length of maximum pool - 5.0
- (2) Length of recreational pool - 4.9
- (3) Length of flood control pool - not applicable

e. Storage (acre-feet)

- (1) Recreation pool - 12,500
- (2) Flood control pool - not applicable
- (3) Test flood pool - 43,368
- (4) Top of dam - 15,000

f. Reservoir Surface (acres)

- (1) Top of dam - 1015
- (2) Test flood pool - 2840
- (3) Flood control pool - not applicable
- (4) Recreation pool - 900
- (5) Spillway crest - 375

g. Dam

- (1) Type - The structure is basically a gravity dam built on a stone foundation with steel stanchions and a concrete superstructure.
- (2) Length - 200' (from past inspection reports)
- 156' (measured)
- (3) Height - 19' (structural height)
- (4) Top width - 16.5'
- (5) Side Slopes - Vertical downstream; approximately 1H:1 3/4V upstream, as shown on design plans
- (6) Zoning - unknown
- (7) Impervious core - unknown

(8) Cutoff - An upstream cutoff wall is reported to have been placed in 1915. (See Appendix B.)

(9) Grout curtain - unknown

h. Diversion and Regulating Tunnel. The regulating tunnels consist of two reinforced concrete boxes approximately 5' x 5' separated by a 30" pier. The tunnels are fitted with gates 27" H x 44" W.

i. Spillway

(1) Type - Concrete spillway with 25 bays of stoplogs.

(2) Length of weir - 126.25' (20 bays @ 5 foot lengths; 2 bays @ 6 foot lengths and 3 bays at approximately 5 foot lengths.)

(3) Crest Elevation - 408.3' MSL (22 bays on either side of gatehouse); 409.6' MSL (3 bays above low-level outlet)

(4) Gates - not applicable

(5) U/S Channel - Milton Three Ponds

(6) D/S Channel - bottom is covered with sand, gravel, and boulders.

(7) General - The 20 bays of stoplog spillway to the west of the gatehouse are comprised of 5 sections separated by 18" wide concrete piers. Each of the above sections is divided into 4 bays separated by 10" wide steel stanchions, and are at invert elevation 408.3' MSL. The 2 bays of stoplog spillway to the east of the gatehouse are also separated by a 10" wide steel stanchion, and at invert elevation 408.3' MSL. The 3 bays of stoplog spillway below the gatehouse are separated by 30" wide concrete piers. These latter bays are at invert elevation 409.6' MSL.

A four foot wide reinforced concrete walkway has been built over the stoplog spillways on both sides of the gatehouse. This access bridge is 1.5 feet thick. The top of the walkway is at elevation 417.6' MSL.

SECTION 2
ENGINEERING DATA

2.1 Design

A search of the files of the New Hampshire Water Resources Board disclosed only a limited amount of recorded information concerning the design of the present outlet facilities at Milton Three Ponds Dam. Plans of the dam re-construction in 1968 were found and used in the hydraulic computations. (See Appendix D.)

2.2 Construction

No pertinent information regarding the actual construction of the present outlet structure at Milton Three Ponds Dam was disclosed.

2.3 Operation

No formal operational procedures were disclosed. However, correspondence reflecting past operational practice were discovered and validated.

2.4 Evaluation

a. Availability. Only a limited amount of data on the actual design and construction of Milton Three Ponds Dam were disclosed.

b. Adequacy. The information obtained from extensive data collection efforts was not adequate in determining the hydraulic characteristics of Milton Three Ponds Dam. Supplemental data established by field investigation was needed to complete the hydraulic analysis. Because of the limited amount of detailed data available, the final assessments and recommendations of this investigation are based on visual inspection and hydrologic and hydraulic analysis.

c. Validity. The visual inspection is consistent with the 1968 re-construction plans.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General. The dam is classified a low dam and impounds an intermediate-size reservoir. The downstream area is sloping and generally open. The USGS has constructed a concrete gaging weir approximately 150 feet downstream. The watershed above the reservoir is heavily wooded. Numerous buildings and homes are located around the perimeter of the reservoir. A vehicular bridge crosses the upstream channel approximately 150 feet upstream from the dam, and a single track railroad bridge also crosses the upstream channel approximately 600 feet upstream from the dam.

b. Dam. The dam was originally built as a combination timber crib dam and dry stone masonry, and according to available correspondence, the dam was increased in height several times to its present height. The upstream cutoff wall was placed in 1915 and the upper timber crib work was replaced with the present concrete channel, catwalk, and stoplog sections in 1968. (See Appendix C - Figures 2, 3 and 4.) The entire dam above the dry stone masonry base consists of stoplog sections. The stoplogs must be manually removed.

The dry stone masonry base indicated only two minor areas of distress on the downstream face, where rocks had become dislodged from the face.

Two openings were observed in the downstream face of the dry stone masonry base which were low-level outlets that were used at one time. The old openings have a dry masonry arch and appear to be plugged some distance behind the downstream face. The present low-level outlet structure is made of concrete and is located near the west abutment.

A portion of the east abutment has been refaced with concrete. The exposed surface of the older concrete has deteriorated little with only the loss of surface laitance, exposure of some of the coarse aggregate, and minor cracking. (See Appendix C - Figure 6.) The top of the original abutment and one portion of the downstream face has spalled and deteriorated to a depth of approximately 1 inch. (See Appendix C - Figure 7.) Minor movement (less than .10 inch) has occurred between the original concrete abutment and the new concrete stoplog structure. Exposed reinforcing was noted in the base of the stoplog slot above

the water line.

The most severe deterioration of the counterfort wall has occurred on the first wall from the left abutment. Approximately 3 inches of the downstream end of the toe of the wall has spalled. (See Appendix C - Figure 8.) Minor loss of surface laitance has occurred on the counterfort walls and spillway apron where the concrete is in continuous contact with the water, exposing some of the coarse aggregate. Evidence of undercutting was noted at the joint between the bottom of the counterfort wall and the base slab. However, the visual inspection could not determine the depth of undercut or effect on the vertical wall reinforcing.

One minor seepage was noted on the downstream face near the contact of the right (west) abutment and the earth embankment.

C. Appurtenant Structures. Low-level control of the dam is accommodated by two sluice gates, 27 inches high by 44 inches wide, with wooden lifting stems. The gates are electrically operated from one electric motor. The gate equipment appeared to be well maintained and is considered to be in good condition. The electrical service was observed to be of adequate size for the given requirements. It was noted that the wiring within the gatehouse is exposed romex wire without double grounding features. The gatehouse appeared to be in good condition.

The concrete walls and base slabs of the gate structure are concrete. The surface of the concrete has eroded and deteriorated from continuous contact with water which has exposed the surface of the coarse aggregate. (See Appendix C - Figure 5.) Visible portions of the concrete mass did not indicate any evidence of movement or instability.

The exposed steel stoplog support beams and embedded angles had not been painted and revealed some surface corrosion, although it did not appear to impair the structural capability of the supports. (See Appendix C - Figure 9.) The stoplogs were noted to be in good condition except for some leakage through the joints and around the ends of the stoplogs.

The concrete service bridge was observed to have one minor longitudinal crack in the vicinity of the embedded wide flange beam, and one expansion joint is deteriorating and spalling the surrounding concrete. (See Appendix C - Figures 10 and 11.)

d. Reservoir Area. The reservoir slopes are gently to steeply sloping and are generally covered with trees and brush. Some open land, in the form of fields and roadways, is adjacent to the reservoir. Numerous buildings, cottages, and homes are located around the lake. Two bridges traverse the upstream channel; a vehicular bridge approximately 150 feet upstream of the dam (See Appendix C - Figure 12.) and a railroad bridge approximately 600 feet upstream. (See Appendix C - Figure 13.) The east shore of the upstream channel is generally covered with trees and brush. (See Appendix C - Figure 14.) One house is located on the east bank, just upstream of the vehicular bridge. Buildings along the west shore are built on the edge of the channel.

e. Downstream Channel. The bottom of the channel downstream of the dam is covered with sand, gravel, and boulders. The channel is generally clear of debris. A concrete gaging weir has been constructed across the channel approximately 150 feet downstream of the dam. Trees and brush are growing adjacent to the channel. (See Appendix C - Figure 16.)

3.2 Evaluation

Based on the visual inspection, the condition of the Milton Three Ponds Dam is good. The potential problems observed during the visual inspection that may affect the long-term integrity of the dam are as follows:

- (1) Large stones that have been dislodged from the downstream face of the dry stone masonry base;
- (2) Minor deterioration of the concrete stoplog structures including local spalling and erosion of concrete, loss of surface laitance, exposure of reinforcing;
- (3) Corrosion of steel stoplog support beams and embedded angle iron;
- (4) Small displacement between old and new concrete on the upstream face at the left abutment;
- (5) Small crack in the service bridge deck; and
- (6) Electrical work in the gatehouse is not double grounded.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures

No formal operational procedures were disclosed. The dam has been owned and operated by the NHWRB since December of 1963. During the summer months, the lake level is maintained by setting the stoplogs at 15.2 feet on the gage (413.8 feet MSL) upstream of the dam, and keeping one of the two waste gates open 3½ inches. In this manner a minimum flow of 20-30 cfs can be supplied to downstream users.

After the summer recreational season the pool is drawn down 6.2 feet by setting the stoplogs at 9 feet on the gage (407.6 feet MSL). Stoplogs are removed from 6 bays so as to gradually lower the lake level. The dam is visited on a weekly basis by the NHWRB.

4.2 Maintenance of Dam

No formal maintenance procedures were disclosed. The NHWRB is responsible for maintaining the dam at Milton Three Ponds.

4.3 Maintenance of Operating Facilities

No formal maintenance schedule for operating mechanisms was disclosed. Both gates are operated in the spring; maintenance is performed at this time if deemed necessary.

4.4 Description of Any Warning System in Effect

No description of any warning system was disclosed.

4.5 Evaluation

The operating and maintenance procedures for Milton Three Ponds Dam, consisting of a weekly program of inspection, should insure that all problems encountered can be remedied within a reasonable period of time. The NHWRB should also establish a surveillance and warning program to follow in the event of floodflow conditions or imminent dam failure.

SECTION 5
HYDROLOGIC AND HYDRAULIC ANALYSIS

5.1 Evaluation of Features

a. Design Data. No original hydrologic and hydraulic design data (circa 1824) were disclosed for Milton Three Ponds Dam. However, hydrologic and hydraulic information, dating from the ownership of the structure by the Public Service Company of New Hampshire to the present ownership by the New Hampshire Water Resources Board, were found and assessed to determine their acceptability in evaluating the overtopping potential of Milton Three Ponds Dam.

b. Experience Data. No information regarding past overtopping of Milton Three Ponds Dam was disclosed.

c. Visual Observations. No visual evidence was disclosed of damage to the structure caused by overtopping at the time of the inspection.

d. Overtopping Potential. Milton Three Ponds Dam is classified as being intermediate in size having a maximum storage of 15,000 acre-feet. The normal recreation level has a surface area of 900 acres, which is equivalent to 1 percent of the watershed.

To determine the hazard classification for Milton Three Ponds Dam, the impact of failure of the dam at maximum pool was assessed using Guidance for Estimating Downstream Dam Failure Hydrographs issued by the Corps of Engineers. The analysis covered the reach extending from the dam to the Milton Leather Board Company Dam in Milton, New Hampshire, a distance of about one-half mile. Failure of Milton Three Ponds Dam at maximum pool would probably result in an increase in stage of approximately 2 feet along the reach and may cause appreciable damage to the Milton Leather Board Company Dam and other lands in the reach.

As a result of the analysis described above, Milton Three Ponds Dam was classified - Significant Hazard. Using OCE Recommended Guidelines for Safety Inspection of Dams, the recommended spillway test flood is the Probable Maximum Flood. The test flow inflow for Milton Three Ponds Dam, having a drainage area of 108 square miles, was determined to be 42,660 cfs (395 csm). The test flood discharge after routing was determined to be 35,000 cfs (324 csm).

Milton Three Ponds Dam is unable to pass the test flood without overtopping. Because the stoplogs would be difficult to remove during a flooding event of this magnitude, the test flood was calculated assuming stoplogs in place. The water depth over the dam embankment was calculated to be 12.8 feet. The spillway capacity, with all stoplogs removed, is approximately 68 percent of the test flood.

SECTION 6
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Inspection. The visual inspection revealed a condition which could lead to structural instability. A few stones appear to have fallen out of two areas of the downstream face of the dry masonry base on which the concrete stoplog structure rests. Further deterioration of the dry masonry base would have an adverse effect on the stability of the dam.

Minor deterioration of the concrete stoplog structure was observed, including local spalling and erosion of concrete, loss of surface laitance, rusting of some upstream stoplog angle irons, exposure of some reinforcing in the concrete, a small displacement between old and new concrete on the upstream face at the left abutment, and a small crack in the service bridge. Proper maintenance should prevent these conditions from developing into a serious stability problem.

One minor seepage was observed at the contact between the dam and the west abutment.

b. Design and Construction Data. Available data show the dimensions of the concrete stoplog structure. However, no detailed information was available concerning the dry masonry base under the concrete stoplog section or the concrete cutoff wall that was apparently poured against the upstream side of the dry masonry base. Therefore, the evaluation of the structural stability must be based primarily on the results of the visual inspection.

c. Operating Records. No operating records pertinent to the structural stability of the dam were disclosed.

d. Post-Construction Changes. According to a letter written by the Public Service Company of New Hampshire on September 29, 1949, the original dam was constructed at some unknown date prior to 1824; the dam was raised 4 feet in 1835 and was then called 9 feet high; the dam was raised 6 feet more in 1835 and this 6 feet was removed in 1847 and replaced at some unknown later date; the dam was raised 2 feet more in 1872 and was then called 16 feet high; and the "cement facing" and gateways were built in 1915. The concrete stoplog structure which comprises the top section of the dam today was built in 1968.

e. Seismic Stability. This dam is in Seismic Zone 2 and hence does not have to be evaluated for seismic stability in accordance with the OCE Recommended Guidelines.

SECTION 7
ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection indicates that Milton Three Ponds Dam is in good condition. The spillway, although unable to pass the test flood without causing overtopping of the dam, is not considered seriously inadequate.

The displacement of a few rocks from the downstream face of the dry masonry base does not appear to have significantly affected the stability of the dam as of the time of the visual inspection. However, this condition should be monitored and repairs should be made if there is evidence of any further deterioration of the dry masonry.

Minor structural deterioration, including cracking, spalling, and erosion of concrete, exposure of reinforcing bars, loss of surface laitance of concrete, a crack in the service bridge, and rusting of the upstream stoplog angle irons should be remedied as part of the routine program of maintenance.

A minor seepage at the contact between the dam and the west abutment does not appear serious. It should be monitored and remedial action taken if needed.

The mechanical and electrical equipment appear to be in good condition.

b. Adequacy of Information. The information available is such that the assessment of the condition of the dam must be based primarily on the visual inspection.

c. Urgency. The recommendations made in 7.2 below should be implemented within 3 years after receipt of this Phase I report by the owner. The operating and maintenance procedures given in 7.3 below should be implemented within one year after receipt of this Phase I report by the owner.

d. Need for Additional Investigation. The information available from the visual inspection is adequate to identify the potential problems which are: overtopping, displacement of rocks from the downstream face, minor structural deterioration, and seepage. These problems require the attention of a competent engineer who will have to make additional engineering studies to design or specify remedial measures

to rectify the problems. If left unattended, the problem could lead to instability of the structure.

7.2 Recommendations

The NHWRB should evaluate further the hydraulics and hydrology of dam and increase the spillway capacity, if necessary.

7.3 Remedial Measures

a. Alternatives. The NHWRB should, as a practical alternative pending implementation of the above recommendations, operate the reservoir at lower levels so as to provide more storage for extreme flood events.

b. Operating and Maintenance Procedures.

(1) Repair annually and maintain the structure to eliminate the effects of cracking, spalling, erosion, and loss of surface laitance of the concrete, and rusting of the stoplog angle irons.

(2) Monitor on a weekly basis the minor seepage at the west abutment and the condition of the dry masonry base.

(3) Replace the romex wiring inside the gatehouse with a steel conduit with insulated conductors and a green grounding conductor (double insulating).

(4) Provide around the clock surveillance during periods of unusually heavy precipitation.

(5) Establish a warning system for alerting downstream residents in case of a flood emergency.

(6) Immediately develop flood regulation procedures relating to the operation of the sluice gates, removal of individual stoplogs, and the removal of stoplog sections under emergency flood conditions. This procedure could be based on rainfall, lake levels or a combination of both.

(7) Continue periodic inspection systems on a bi-annual frequency.

APPENDIX A
CHECK LIST - VISUAL INSPECTION

VISUAL INSPECTION CHECKLIST

PARTY ORGANIZATION

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

TIME 2:00 P.M.

WEATHER Sunny, hot

W.S. ELEV. 413.8 U.S. 398.6 DN.S.

PARTY:

- | | |
|---------------------------------------|---------------------------------------|
| 1. <u>Warren Guinan</u> | 6. <u>Harold Wilcox (6 June 1978)</u> |
| 2. <u>Robert Langen</u> | 7. _____ |
| 3. <u>Stephen Gilman</u> | 8. _____ |
| 4. <u>Ronald Hirschfeld</u> | 9. _____ |
| 5. <u>John Falcione (6 June 1978)</u> | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Hydrology/Hydraulics</u>	<u>R. Langen</u>	
2. <u>Structural Stability</u>	<u>S. Gilman</u>	
3. <u>Soils & Geology</u>	<u>R. Hirschfeld</u>	
4. <u>Mechanical</u>	<u>J. Falcione</u>	
5. <u>Electrical</u>	<u>H. Wilcox</u>	
6. _____	_____	_____
7. _____	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H. DATE June 19, 1978

PROJECT FEATURE Dam Embankment NAME

DISCIPLINE NAME

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	Good, see attached notes.
Current Pool Elevation	
Maximum Impoundment to Date	
Surface Cracks	
Pavement Condition	
Movement or Settlement of Crest	
Lateral Movement	
Vertical Alignment	
Horizontal Alignment	
Condition at Abutment and at Concrete Structures	
Indications of Movement of Structural Items on Slopes	No visible movement.
Trespassing on Slopes	
Sloughing or Erosion of Slopes or Abutments	
Rock Slope Protection - Riprap Failures	
Unusual Movement or Cracking at or near Toes	
Unusual Embankment or Downstream Seepage	
Piping or Boils	
Foundation Drainage Features	
Toe Drains	
Instrumentation System	

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H. DATE June 19, 1978
 PROJECT FEATURE Upstream Channel NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	
Slope Conditions	Gentle slopes covered with grass, trees and brush, vertical slopes at buildings
Bottom Conditions	Not visible
Rock Slides or Falls	None
Log Boom	None
Debris	None
Condition of Concrete Lining	Not visible
Drains or Weep Holes	None
b. Intake Structure	
Condition of Concrete	Surface laitance eroded
Stop Logs and Slots	Good condition, some leakage

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

PROJECT FEATURE Control Tower

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	Wooden gatehouse
a. Concrete and Structural	
General Condition	Good
Condition of Joints	No visible movement
Spalling	Little on older concrete section See attached notes
Visible Reinforcing	
Rusting or Staining of Concrete	None visible
Any Seepage or Efflorescence	Little efflorescence at constr. joints
Joint Alignment	Good
Unusual Seepage or Leaks in Gate Chamber	None visible
Cracks	None visible
Rusting or Corrosion of Steel	None visible
b. Mechanical and Electrical	
Air Vents	Two wooden sluice gates 27" high by 44" wide lifting stems-electrically operated one motor used by removing belts from Gate #1 and shifting them to sheave of Gate #2. Gates and equipment well maintained and in good condition. No emergency power or lightning protection system. Electrical service - 120/240 volt, 1 phase, 3-wire, 60 ampere. Electrical service deemed to be of adequate size. Panel board consists of 1-50 amp, 2 pole circuit breaker, serving 1 horsepower reversible motor, 1-20 amp circuit breaker servicing lights, and 1-20 amp circuit breaker servicing outlet receptacles. Size and quantity of circuit breakers are sufficient; space available on panel board to add circuits if required. Wiring in gate-house is romex. Should be replaced with steel conduit and insulating conductors, with green grounding conductor.
Float Wells	
Crane Hoist	
Elevator	
Hydraulic System	
Service Gates	
Emergency Gates	
Lightning Protection System	
Emergency Power System	
Wiring and Lighting System in Gate Chamber	

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

PROJECT FEATURE Outlet Conduit

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - TRANSITION AND CONDUIT

Not visible

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

PROJECT FEATURE Stoplog Structure

NAME _____

IS IPIRNE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Good
Rust or Staining	None visible
Spalling	Little on old concrete
Erosion or Cavitation	Little visible
Visible Reinforcing	None visible
Any Seepage or Efflorescence	None visible
Condition at Joints	Good - no visible movement
Drain holes	None
Channel	
Loose Rock or Trees Overhanging Channel	A few trees at edges of wide discharge channel
Condition of Discharge Channel	Good

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

PROJECT FEATURE Spillway Weir

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Good
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	A few on both banks
Floor of Approach Channel	Not visible
b. Weir and Training Walls	
General Condition of Concrete	Generally good-see attached notes
Rust or Staining	
Spalling	Little
Any Visible Reinforcing	
Any Seepage or Efflorescence	
Drain Holes	None observed
c. Discharge Channel	
General Condition	Good
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	Some on west bank
Floor of Channel	Boulders, sand, gravel
Other Obstructions	Measuring weir downstream of dam

PERIODIC INSPECTION CHECK LIST

PROJECT Milton Three Ponds Dam, N.H.

DATE June 19, 1978

PROJECT FEATURE Service Bridge

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - SERVICE BRIDGE

See attached notes

a. Super Structure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Good condition

Under Side of Deck

Secondary Bracing

Deck

Good

Drainage System

Railings

Good

Expansion Joints

Paint

Good

b. Abutment & Piers

General Condition of Concrete

Good

Alignment of Abutment

Approach to Bridge

Condition of Seat & Backwall

PROJECT Milton Three Ponds Dam, NH

DATE June 19, 1978

PROJECT FEATURE Reservoir

NAME R. Langen

AREA EVALUATED	REMARKS
Stability of Shoreline	Good
Sedimentation	No visible problems
Changes in Watershed Runoff Potential	Minor
Upstream Hazards	2 road bridges and 1 RR bridge with small vertical opening; building at pond edge on west side
Downstream Hazards	Several dams on river downstream
Alert Facilities	None observed
Hydrometeorological Gages	Staff gage
Operational & Maintenance Regulations	None observed

MILTON THREE PONDS DAM
ADDITIONAL NOTES

Monolith #1 - Left Abutment

1. The monolith is cast against the concrete abutment placed there many years previous. New concrete - good condition.

2. There is evidence of movement - open crack between new concrete and old on upstream face.

3. There is some spalling of cap on old concrete abutment. Old and new concrete that is now or has been submerged has lost surface laitance.

4. Upstream stoplog slot has exposed reinforcing - little rusting and staining.

5. Downstream face has tie holes left unfilled.

6. Joint at end of service bridge and abutment - some spalling.

Monolith #2

1. Downstream end spalled/eroded - reinforcing exposed.

2. Surface laitance gone where exposed to moving water.

3. Expansion joint in service bridge is spalling - joint material deteriorating.

4. There is visual evidence of little eroding of concrete at the base of wall and slab.

5. Some rusting of embedded stoplog angle iron.

Monolith #3, #4, #5, #6, #7

1. Some eroding of concrete at wall/slab joint

2. Some eroding at end of Monolith wall end

3. Generally good condition

4. Surface laitance gone on concrete

5. Exposed joint at #5 - caulking gone; cork exposed.

Steel Stoplog Support

The steel has not been painted resulting in some surface corrosion.

Stoplogs

The stoplogs are in generally good condition with numerous minor leaks.

Monolith #8 - Right Abutment

1. Old concrete surface laitance gone. Wall cracked longitudinally with leaching.
2. Crack at joint between service bridge and abutment filled with caulking. Good condition, no apparent movement.

Service Bridge

The deck is cracked longitudinally in area of embedded beam.



NEW HAMPSHIRE WATER CONTROL COMMISSION

REPORT ON DAM INSPECTION

TOWN Milton DAM NO. 16106 STREAM Salmon Falls River

OWNER Public Service Co. of N.H. ADDRESS Manchester N.H.

In accordance with Section 20 of Chapter 133, Laws of 1937, the above dam was inspected by me on July 29, '50 accompanied by _____

NOTES ON PHYSICAL CONDITION

Abutments Good

Spillway Small Fir came & down stream broke anchor into a rotten horizontal member

Gates operable

Other _____

CHANGES SINCE LAST INSPECTION None

FUTURE INSPECTIONS 1/65

This dam (is) (~~is not~~) a menace because of ponding and property downstream

REMARKS Water 5 1/2' from top of non-overflow concrete.

Copy to Owner	Date

Francis G. Hance
INSPECTOR

(Additional Notes Over)

1037 Elm Street
Manchester, N. H.

CONTRACTOR

NO.

APPLICATION

RECEIVED

INVESTIGATED BY

DATE

IF DAM IMPROPERLY CONSTRUCTED IT Would

BE A MENACE TO THE PUBLIC SAFETY

IS DAM SUBJECT TO PROVISIONS OF P. L. CHAP. 218, SECTS. 15-26? Yes

PLANS &
SPECIFICATIONS

RECEIVED

CHECKED BY

DATE

APPROVED BY COMMISSION

COMMISSION CONSTRUCTION INSPECTOR

FINAL CONSTRUCTION APPROVAL

CHARGES

PAID

IS DAM SUBJECT TO PERIODIC INSPECTION? Yes

DAM INSPECTION RECORD

DATE	INSPECTOR	REPORT	CHARGES	PAID	DATE	INSPECTOR	REPORT	CHARGES	P
10/12/35	A.C. Blake	10/14/35	\$10.00	10/24/35					
	Condition--Good								

FORM E

PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-4822

TOWN	HILTON	TOWN NO.	6	STATE NO.	72 161
RIVER	Salmon Falls River	POND AREA			
DRAINAGE AREA	115 Sq. Mi.	FOUNDATION NATURE OF	Ledge		
TYPE	Gravity				
MATERIALS OF CONSTRUCTION	Stone, Timber, Concrete				
PURPOSE	POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY				
HEIGHTS, TOP OF DAM	16'	TOP OF DAM TO SPILLWAY CRESTS	8'		
DOWN TO BED OF STREAM	14'-8"	20'-7"	102'-4"	LENGTH OF DAM	Approx. 200'
SPILLWAYS LENGTHS	5'	8'	5'		
DOWN BELOW TOP OF DAM	Removable	24 Bays			
FLASHBOARDS	5'-7"	6'-4"			
HEIGHT ABOVE CREST					
OPERATING HEAD		TOP OF FLASHBOARDS TO N. T. W.			
CREST TO N. T. W.					
WHEELS, NUMBER					
KINDS & H. P.					
GENERATORS, NUMBER					
KINDS & K. W.					
H. P. 75 P. C. TIME		H. P. 75 P. C. TIME			
100 P. C. EFF.		100 P. C. EFF.			
REFERENCES CASES					
PLANS INSPECTIONS					
REMARKS					

PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-4822

TOWN	Milton	TOWN NO	6	STATE NO	10155
RIVER	Salmon Falls River				
STREAM					
DRAINAGE AREA	115 61. 1.	POND AREA			
DAM TYPE	Gravity	FOUNDATION NATURE OF	Ledge		
MATERIALS OF CONSTRUCTION	Stone, Timber, Concrete				
PURPOSE OF DAM	POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY				
HEIGHTS, TOP OF DAM TO BED OF STREAM	16'	TOP OF DAM TO SPILLWAY CRESTS	8'		
SPILLWAYS, LENGTHS	14'-8"	20'-7"	102'-4"	LENGTH APPROX. 200'	
DEPTHS BELOW TOP OF DAM	5'	8'	5'		
FLASHBOARDS	Removable 24 Bays				
TYPE HEIGHT ABOVE CREST	5'-7" - 6'-4"				
OPERATING HEAD					
CREST TO N. T. W.	TOP OF FLASHBOARDS TO N. T. W.				
WHEELS, NUMBER					
KINDS & H. P.					
GENERATORS, NUMBER					
KINDS & K. W.					
H. P. 90 P. C. TIME	H. P. 75 P. C. TIME				
100 P. C. EFF.	100 P. C. EFF.				
REFERENCES, CASES.					
PLANS, INSPECTIONS					
REMARKS					

OWNER- Public Service Company of N. H.

CONDITION- Good

MENACE- Yes. Will be subject to periodic inspection.

To the Public Service Commission:

The foregoing memorandum on the above dam is submitted covering inspection made October 9, 1935, according to notification to owner dated October 7, 1935, and bill for same is enclosed.

Samuel J. Lord
Hyd. Eng.

Oct. 14, 1935
Copy to Owner

INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

PAID	<u>Ccean</u>	NO.	<u>6-72-54522</u>
RIVER	<u>Tupper Ponds</u>	MILES FROM MOUTH	<u>D.A.SQ. MI. 46 1/2</u>
TOWN	<u>Huron</u>	OWNER	<u>Public Service Co. of N.H. Manchester</u>
LOCAL NAME	<u>OP DAM</u>		
BUILD		DESCRIPTION	<u>Gravity - Stone Tupper Concrete</u>

DAM AREAS-ACRES { 1400 P.S.Co # 12 P.S.Co 13,330 P.S.
 HEIGHT-ROP TO BED OF STREAM-FT. 816.6 V.P. DRAWN TO 12 WRB FLOOD CAPACITY-ACRE FT. 28,500 WRB
 MAX. MIN.
 OVERALL LENGTH OF DAM-FT. 200± MAX. FLOOD HEIGHT ABOVE CREST-FT. _____
 PERMANENT CREST ELEV. U.S.G.S. _____ LOCAL GAGE
 MIN. WATER ELEV. U.S.G.S. 107 WRB LOCAL GAGE
 DAM LENGTHS-FT. 20, 583, 102, 33 and 14. 61 FREEBOARD-FT. 8 and 6 and 5
 FREEBOARDS-TYPE, HEIGHT ABOVE CREST removable 5.583 - 13 days 6.33
 DAM NO. WIDTH MAX. OPENING DEPTH SILL BELOW CREST

Flood of hard overspillway 8.7.
Into Salmon Falls R, Piscataqua R, Atlantic Ocean.

Assumed $C = 2.8$

FOR DEVELOPMENT

[illegible]

Conservation, Public Utilities

* Note: Must not be drawn below gft. on the gauge
June, July & August. Full pond = 16 $\frac{1}{2}$ ft. on gauge. E.S.C.

10/7/35

8640

TYPE OF DAM	H	W	H	CONDITION	VOID WATER	INTERFERE	INJECTION DATE	OWNER INTERFERES
GRAVITY	165'		14'	POOR	YES	YES	10-8-35	YES
"	240'		17'	GOOD	YES	YES	10-8-35	YES
100+5000	195'		21'	GOOD	YES	YES	10-9-35	YES
GRAVITY	312'		35'	GOOD	YES	YES	10-8-35	YES
"	120'		13'	FAIR	YES	YES	10-9-35	YES
GRAVITY	240'		16'	GOOD	YES	YES	10-7-35	YES
GRAVITY	110'		11'	FAIR	YES	YES	10-7-35	YES
GRAVITY	120'		17'	FAIR	YES	YES	10-9-35	YES
"	240'		16'	POOR	YES	NO	10-9-35	NO
GRAVITY	150'		14'	POOR	NO	NO	10-7-35	NO
"	170'		10'	FAIR	YES	YES	10-9-35	YES
"	140'		40"	FAIR	YES	YES	10-8-35	YES
GRAVITY	260'		8'	GOOD	YES	NO	10-8-35	NO
"				GOOD	YES	NO	10-8-35	NO
GRAVITY				POOR	NO			

NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON DAMS IN NEW HAMPSHIRE

LOCATION

STATE NO. 161.06

Town Milton: County Stratford
Stream Salmon Falls R.
Basin-Primary Disc. 11412: Secondary Salmon Falls R.
Local Name _____
Coordinates—Lat. 43° 25' - 1200: Long. 71° 0' - 0500

GENERAL DATA

Drainage area: Controlled _____ Sq. Mi.: Uncontrolled _____ Sq. Mi.: Total 115 ^{112.WRB} Sq. Mi.
Overall length of dam 200 ft.: Date of Construction _____
Height: Stream bed to highest elev. 121 ft.: Max. Structure 81 ✓ 7 ft.
Cost—Dam _____: Reservoir _____

DESCRIPTION

Gravity

Waste Gates Stone Timber Concrete Foundation ledge

Type _____
Number _____: Size _____ ft. high x _____ ft. wide
Elevation Invert _____: Total Area _____ sq. ft.
Hoist _____

Waste Gates Conduit

Number _____: Materials _____
Size _____ ft.: Length _____ ft.: Area _____ sq. ft.

Embankment

Type _____
Height—Max. _____ ft.: Min. _____ ft.
Top—Width _____: Elev. _____ ft.
Slopes—Upstream _____ on _____: Downstream _____ on _____
Length—Right of Spillway _____: Left of Spillway _____

Spillway

Materials of Construction _____
Length—Total 1.11.8" 20' 3.2 1.02 10' Net _____ ft.
Height of permanent section—Max. 5' ft.: Min. _____ ft.
Flashboards—Type Removable 5'7" 24 bays 6'4": Height _____ ft.
Elevation—Permanent Crest _____: Top of Flashboard _____
Flood Capacity 5550 cfs.: _____ cfs/sq. mi.

Accessments


Materials: _____
Flashboard: Max. 81 ft.: Min. _____ ft.

Headworks to Power Devel.—(See "Data on Power Development")


OWNER 112.05 MW Manchester, N.H.

REMARKS Condition good Subject to inspection

Drawn By GWS B-6 Date 3/29



LOCATION MAP
Milton Three Power Dam
Scale 1/2 mi



GENERAL SITE PLAN
Scale 1/2 mi



MILTON THREE POWER
MILTON

GENERAL PLANS, ELEVATION & SECTION


NEW HAMPSHIRE WATER RESOURCES BOARD

CONCORD, N.H.

Sheet 1 of 4



APPENDIX C
PHOTOGRAPHS



Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
MILTON THREE PONDS DAM			
PHOTO INDEX			
SALMON FALLS RIVER		NEW HAMPSHIRE	
		SCALE: NOT TO SCALE	
		DATE: AUGUST 1978	



Figure 2 - Downstream face of Milton Three Ponds Dam.



Figure 3 - Looking along the center of Milton Three Ponds Dam from the vicinity of the east abutment.



Figure 4 - Upstream face of Milton Three Ponds Dam.



Figure 5 - Looking at the low-level outlets near the west end of the dam. The abandoned masonry arch outlets are to the right of the concrete outlet works.




Figure 6 - Close-up view of the sidewall at the east abutment.




Figure 7 - Downstream face of the east abutment.




Figure 8 - Close-up view of the downstream face of the dam. Note the spalling on the nearest countefort.




Figure 9 - Looking upstream at the stoplog support beams.




Figure 10 - Crack in top of the concrete service bridge.




Figure 11 - Spalling at an expansion joint in the concrete service bridge.



Figure 12 - Looking upstream at the vehicular bridge, approximately 150 feet upstream of the dam.



Figure 13 - Looking upstream at the railroad bridge, approximately 600 feet upstream of the dam.



Figure 14 - Looking upstream from the dam at the east shore of the approach channel.



Figure 15 - Looking upstream at the west shore of the approach channel.




Figure 16 - Looking at the downstream channel
from the east abutment of the dam.

APPENDIX D
HYDROLOGY/HYDRAULICS

HIDROLOG / HIDROLOGIA
MILTON THREE POINTS DAM

1/15

STEP 1: Probable Maximum Flood Determination (PMF)
RE: Preliminary Guidance for Estimating
Maximum Probable Discharges in Phase I
Dam Safety Investigations, NED-COE,
March 1978.

Using Flat & Coastal Curve to determine PMF
Peak Inflow.

DA = 108 mi² - USGS measured & published

$$\text{PMF} = 395 \text{ cfs/sq.mi} \times 108 \text{ sq.mi.}$$

$$\text{PMF} = \underline{42,660 \text{ cfs}} \quad (\text{PEAK INFLOW})$$

Hydraulic Assumptions:

1 waste gate closed

1 gate open 3 1/2"

Normal water level - 15.2 gage = 413.81 MSL

Rating Curve Comps:

@ elev. 413.81 STOPLOG FLOW = 0 cfs
Gate 27" H x 44" W open 3 1/2"

$$K_f = \frac{(29.1)(n^2)(L)}{R^{4/3}}$$

$$= \frac{(29.1)(.02)^2(16.6)}{(0.135)^{4/3}}$$

$$= 2.79$$

$$A = 3 \frac{1}{2}'' \times 44'' = 1.07 \text{ ft}^2$$

$$P = 7'' + 88'' = 7.92 \text{ ft}$$

$$R = \frac{A}{P} = 0.135$$

$$L = 16.6'$$

$$n = 0.02$$

Entrance & exit losses ≈ 1.10

$$\text{Total } K = 3.89$$

$$3.89 = \frac{1}{C^2}$$

$$C = 0.51$$

2/15

$$Q = CA\sqrt{2gh}$$

$$\begin{aligned} C &= 0.51 \\ A &= 1.07 \\ g &= 32.2 \\ h &= 13.6 \end{aligned}$$

$$= (0.51)(1.07)\sqrt{64.4 \cdot 13.6}$$

$$= \underline{16.1 \text{ cfs}} = \text{GATE CAPACITY @ NORMAL POOL}$$

@ elev 416.11 = LC OF WALKWAY = low pt to right

GATE CAPACITY

$$Q = CA\sqrt{2gh}$$

$$= (0.51)(1.07)\sqrt{(64.4)(15.9)}$$

$$= 17.5 \text{ cfs}$$

STORLOG SPILLWAY

$$Q = CLH^{3/2}$$

$$= (2.8)(126.25)(2.3)^{3/2}$$

$$= 1233 \text{ cfs}$$

$$\text{TOTAL } Q = 17.5 + 1233 = \underline{1250 \text{ cfs}}$$

@ elev 416.8 = LOW PT TO LEFT OF DAM

GATE CAPACITY

$$Q = (0.51)(1.07)\sqrt{(64.4)(16.59)}$$

$$= 17.8 \text{ cfs}$$

STORLOG SPILLWAY

$$Q = CA\sqrt{2gh}$$

$$K = \frac{1}{C^2} ; K_f = \frac{(29.1)(n^2)(L)}{R^{4/3}} ; R = \frac{A}{P}$$

$$A = (126.25)(2.3) = 290.4 \text{ ft}^2$$

D-3

3/15

$$P = 2(126.25) + 2(2.3) + 24(2.3) = 312.3$$

$$R = \frac{290.4}{312.3} = 0.93$$

$$K_f = \frac{(29.1)(0.015)^2(0.33)}{(0.93)^{4/3}} = 0.002$$

$$\text{entrance \& exit} = 1.1 \Rightarrow \text{say } K = 1.1$$

$$K = \frac{1}{C^2} \quad 1.1 = \frac{1}{C^2} \quad C = 0.95$$

$$\begin{aligned} Q &= CA \sqrt{2gh} \\ &= (0.95)(290.4) \sqrt{(64.4)(3.03)} \\ &= 3856 \text{ cfs} \end{aligned}$$

OVERLAND FLOW

$$\begin{aligned} Q &= CLH^{3/2} \\ &= (2.6)(6.5)(0.7)^{3/2} = 9.9 \text{ cfs} \end{aligned}$$

$$\text{TOTAL } Q = 17.8 + 9.9 + 3856 = \underline{\underline{3885 \text{ cfs}}}$$

@ elev 417.61 = TOP OF CONCRETE WALKWAY

WING CAPACITY

$$\begin{aligned} Q &= (0.51)(1.07) \sqrt{(64.4)(17.4)} \\ &= 18.3 \text{ cfs} \end{aligned}$$

STOPLOG SPILLWAY

$$\begin{aligned} Q &= (0.95)(290.4) \sqrt{(64.4)(3.84)} \\ &= 4338 \text{ cfs} \end{aligned}$$

4/15

OVERLAND FLOW - LEFT $Q = CLH^{3/2}$

$$Q = (2.6)(18)(0.6)^{3/2} + (2.6)(75.5)(0.2)^{3/2}$$

$$= 21.8 + 17.6 = \underline{39.4}$$

OVERLAND FLOW - RIGHT $Q = CLH^{3/2}$

$$Q = (2.6)(12.5)(1.2)^{3/2} + (2.6)(33)(0.2)^{3/2}$$

$$= 42.7 + 7.7 + 2.6(19)(0.2)^{3/2}$$

$$= 42.7 + 7.7 + 23.0 = \underline{73.4 \text{ cfs}}$$

$$\text{TOTAL } Q = 18.3 + 4338 + 39.4 + 73.4 = \underline{4470 \text{ cfs}}$$

@ elev. 418.2

GATE CAPACITY

$$Q = (0.51)(1.07)\sqrt{(64.4)(18.0)}$$

$$= 18.6$$

STOPLOG SPILLWAY

$$Q = (0.95)(290.4)\sqrt{64.4(4.43)}$$

$$= 4660$$

OVERLAND BFLOW
TOP WALKWAY

$$Q = 39.4 + 73.4 = 112.8$$

Q OVERTOP DAM

$$Q = CLH^{3/2}$$

$$= (2.7)(386)(0.6)^{3/2} = 485$$

$$\text{TOTAL } Q = 18.6 + 4660 + 112.8 + 485 = \underline{5275 \text{ cfs}}$$

D-5

@ elev. 418.9

GATE CAPACITY

$$Q = (0.51)(1.07) \sqrt{64.4(18.7)} = 18.9$$

SEEPLOG SPILLWAY

$$Q = (0.95)(290.4) \sqrt{64.4(5.13)} = 5014$$

OVERLAND FLOW

$$Q = 112.8$$

BELOW WALKWAY

Q OVERTOP

$$Q = CLH^{3/2}$$

$$= (2.7)(428.5)(0.7)^{3/2} + 485 = 1163$$

$$\text{TOTAL } Q = 18.9 + 5014 + 112.8 + 1163 = 6310 \text{ cfs}$$

@ elev. 420.3

GATE CAPACITY

$$Q = 4.38 \sqrt{20.1} = 19.6$$

SEEPLOG

$$Q = 2214 \sqrt{6.53} = 5658$$

BELOW WALKWAY

$$Q = 112.8$$

$$Q_{\text{OVERTOP}} = (2.7)(446)(0.1)^{3/2} + (2.7)(462)(1.2)^{3/2} + 1163$$

$$= 38.1 + 1848.9 + 1163 = 3050 \text{ cfs}$$

$$\text{TOTAL } Q = 19.6 + 5658 + 112.8 + 3050 = \underline{\underline{8840}}$$

@ elev. 424.6

GATE

$$Q = 4.38 \sqrt{20.1 + 4.3} = 21.6$$

SEEPLOG

$$Q = 2214 \sqrt{6.53 + 4.3} = 7286$$

BELOW WALKWAY

$$Q = 112.8$$

$$Q_{\text{OVERTOP}} = (2.7)(476)(0.2)^{3/2} + 2.7(509)(4.1)^{3/2} + 3050$$

$$Q = 115 + 11409 + 3050 = 14574$$

$$\text{TOTAL } Q = 21.6 + 7286 + 112.8 + 14574 = \underline{\underline{22000}}$$

① elev. 431.1

$$\begin{aligned} \text{GATE} \quad Q &= 4.38 \sqrt{24.4 + 6.5} = 24.3 \\ \text{STOPLOG} \quad Q &= 2214 \sqrt{10.83 + 6.5} = 9217 \end{aligned}$$

$$\text{wkwuy} \quad Q = 112.8$$

$$Q_{\text{over top}} = (2.7)(554)(1)^{3/2} + (2.7)(576)(0.4)^{3/2} + (2.7)(595)(5.1)^{3/2} + 14574 =$$

$$= 1496 + 393 + 18503 + 14574 = 34966$$

$$\text{TOTAL } Q = 24.3 + 9217 + 112.8 + 34966 = \boxed{44320}$$

① elev. 430

$$\text{GATE} = Q = 4.38 \sqrt{24.4 + 5.4} = 23.9$$

$$\text{STOPLOG} = Q = 2214 \sqrt{10.83 + 5.4} = 8919$$

$$\text{wkwuy} \quad Q = 112.8$$

$$Q_{\text{over top}} = 1496 + 393 + 14574 + (2.7)(592.5)(4)^{3/2} = 29261$$

$$\text{TOTAL } Q = 23.9 + 8919 + 112.8 + 29261 = \boxed{38317}$$

① elev. 430.8

$$\text{GATE} \quad Q = 4.38 \sqrt{29.8 + 0.8} = 24.2$$

$$\text{STOPLOG} \quad Q = 2214 \sqrt{16.23 + 0.8} = 9137$$

$$\text{wkwuy} \quad Q = 112.8$$

$$Q_{\text{out}} = 1496 + 212 + 14754 + 17(600) + 2,12$$

$$= 33641$$

$$\text{Total } Q = 24.2 + 9137 + 112.8 + 33641 = 42915$$

$$\text{① PMF inflow } (42,660) \text{ elev.} = 430.8$$

Volume of Surcharge

$$\text{STOR @ normal} = 13330 \text{ AF}$$

$$\text{STOR @ PMF } > 430.8 = 49500 \text{ AF}$$

$$\therefore \text{surcharge-stor} = 36170 \text{ AF}$$

$$16.10 \text{ AF} \times \frac{1}{108 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ A}} = 0.523'$$

$$0.523' = 6.28'' \text{ runoff over basin}$$

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{\text{STOR}_1}{19}\right)$$

$$= 42,660 \times \left(1 - \frac{6.28}{19}\right)$$

$$= 28,560 \text{ cfs}$$

Surcharge height to pass $Q_{p2} = 28,560 \text{ cfs}$
from rating curve - elev. = 426.7

$$\text{Stor @ } 426.7 = 37250 \text{ AF}$$

$$\text{stor @ } 414.6 = 13330 \text{ AF}$$

$$\therefore \text{STOR}_2 = 23,920 \text{ AF}$$

$$23,920 \times \frac{1}{108 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ A}} = 0.346'$$

$$0.346' = 4.15''$$

$$\left. \begin{array}{l} \text{STOR}_1 = 6.28'' \\ \text{STOR}_2 = 4.15'' \end{array} \right\} \text{AVE} = 5.215''$$

$$4.15'' \times 108 \text{ mi}^2 \times \frac{1}{12} \times \frac{640 \text{ A}}{1 \text{ mi}^2} = 30,038 \text{ AF}$$

8/15

From storage / elev. curve


$$30,038 + 13,330 = 43,368 \text{ AF}$$

$$@ 43,368 \text{ AF} - \text{elev.} = 429.0$$

$$@ 429.0 \text{ MSL} - 35,000 \text{ cfs}$$

$$\underline{Q_{p3} = PMF = 35,000 \text{ cfs @ } 429.0' \text{ MSL}}$$

$$\frac{1}{2} Q_{p3} = 17,500 \text{ cfs} \Rightarrow 423.3' \text{ MSL}$$




MILTON THREE PONDS
 RATING CURVE
 B0 8/7/78

DISCHARGE IN CFS

ELEVATION IN FEET

10/15

MILTON THREE PONDS
STORAGE CURVE
BO 8/7/78



ELEVATION IN FEET (MSL)
D-11

STORAGE IN AF

FROM THREE PONDS
STOPLOG CAPACITIES
8/15/78

11/15

$$Q = CLH^{3/2}$$

① @ RECREATIONAL POOL = 413.8

22 BAYS @ INVERT 408.3

3 BAYS ABOVE WASTE GATES @ INVERT 409.6

$$Q = CLH^{3/2}$$

$$Q = (2.9)(12 + 100)(413.8 - 408.3)^{3/2} = 4190 \text{ cfs}$$

$$(2.9)(14.25)(413.8 - 409.6)^{3/2} = 356 \text{ cfs}$$

$$4546 \text{ cfs}$$

SAY 4550 cfs

② @ MAXIMUM POOL = 416.2

@ this elevation - stoplog opening acts like orifice under pressure flow.

$$Q = CA\sqrt{2gh}$$

FOR LARGE BAYS

$$K = \frac{1}{C^2}$$

$$K_f = \frac{(29.1)(n^2)(L)}{R^{4/3}}$$

$$R = \frac{A}{P}$$

$$1.1 = \frac{1}{C^2}$$

$$A_f = 112 \times (416.1 - 408.3) = 874$$

$$C = 0.95$$

$$P = (2 \times 112) + (22 \times 7.8) = 396$$

$$R = 2.21 \quad R^{4/3} = 2.88$$

$$K_f = \frac{(29.1)(0.015)^2(0.33)}{2.88} = \text{negligible}$$

entrance < exit ≈ 1.1

12/15

$$Q_1 = CA \sqrt{2gh}$$

$$= (0.95)(874) \sqrt{64.4 (416.2 - 408.3 + 2.6)} = 21,590$$

$$Q_2 = CA \sqrt{2gh}$$

← FOR SMALLER BAYS

$$A = 14.25 \times (416.1 - 409.6) = 93$$

$$P = (2 \times 14.25) + (3 \times 6.8) = 49$$

$$R = 1.90$$

$$R^{4/3} = 2.36$$

$$K_f = \frac{(29.1)(0.015)^2 (0.33)}{2.36} = \text{negligible}$$

$$\therefore C = 0.95$$

$$Q_2 = (0.95)(93) \sqrt{(64.4)(416.2 - 409.6 + 2.2)} = 2103$$

$$\text{TOTAL } Q \text{ thru stoplog Bays} = 21590 + 2103 = 23690$$

$$\boxed{\text{SAY } 23700 < Q_s}$$

JOB NO. 24-03 Flood Control

RES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29
SCALE

DIS Hazard Analysis - using maximum pool elevation of 416.2 to determine breach discharge.

Storage @ time of failure - 15,000 ac-ft

$$Q_B = \frac{2}{27} W_b \sqrt{g} H^{3/2}$$

$$Q_B = \frac{2}{27} (0.4 \times 156) (\sqrt{32.2}) (416.2 - 408.6)^{3/2}$$

$$Q_B = 2198$$

upstream bed

Q THRU REST OF DAM:

$$\text{gate} = 18 \text{ cfs}$$

$$\text{stoplog} = 2.8 \cdot 90 \cdot (2.3)^{3/2} = 879 \text{ cfs}$$

$$18 \text{ cfs}$$

$$897 \text{ cfs}$$

$$\text{Total } Q = Q_{\text{DAM}} + Q_B = 3095 \text{ cfs}$$

@ maximum pool - stoplog capacity with all stoplogs removed = 23,700 cfs

PMF discharge - 35,000 cfs

1/2 PMF - 17,500 ∴ analysis only needs

to be done @ maximum pool breach.

Use rating curve established from typical section of downstream reach.

Q of 3095 cfs - Stage 4.7'

Reach length - 2112'

$$\text{Area @ 4.7' stage} - A = \frac{1}{2} 4.7 (75 + 220) = 693 \text{ ft}^2 \approx 34 \text{ AC-FT}$$

Since stage in reach is so minimal as


compared to total stage use stage of

4.7' ≈ 5' stage @ next dam downstream

Hazard Classification - based on 5' increase

Antecedent discharge ≈ 1300 cfs - Stage 3'

Increase in stage ∴ 2' at next d/s dam



Milton Three Ponds
Dis Hazard Rating Curve
8/22/78

10/3/78

15/15

Milton, Three Pond Dam

Calculate gate capacity @ normal pool
elevation of 413.8

2 gates - 21" H x 44" W

$$Area = 8.25 \text{ ft}^2$$

$$WP = 11.83$$

$$R = 0.70$$

$$K_f = \frac{(29.1)(0.02)^2(16.6)}{(0.70)^{4/3}} = 0.31$$

$$\text{entrance \& exit losses} = 1.10$$

$$K_{TOTAL} = 1.41$$

$$1.41 = \frac{1}{C^2}$$

$$C = 0.84$$

$$Q = CA\sqrt{2gh}$$

$$C = 0.84$$

$$A = 8.25$$

$$g = 32.2$$

$$h = 413.8 - 402.3 = 11.5$$

$$Q = (0.84)(8.25)\sqrt{2(32.2 \times 11.5)}$$

$$= 188.6 \approx 190 \text{ cfs / each gate}$$

Total discharge capacity of both gates
@ normal pool = $190 \text{ cfs} \times 2 = \underline{\underline{380 \text{ cfs}}}$

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 11-14-01 BY 60322 UCBAW



INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	IDENTITY NUMBER	CONGR. DIST.	STATE	COUNTY	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE DAY MO YR
NH	320	NED	NH 017 01			MILTON THREE PONDS DAM	4324.6	7059.2	08SEP78

POPULAR NAME	NAME OF IMPOUNDMENT
MILTON DAM	MILTON THREE PONDS

REGION BASIN	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	DIST. FROM DAM (MI.)	POPULATION
01 04	SALMON FALLS RIVER	MILTON	0	1859

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRUCT. HEIGHT (FT.)	HYDRAUL. HEAD (FT.)	IMPOUNDING CAPACITIES (ACRE-FT.)	DIST. OWN	FED R	PRV/FED	SCS A	VER/DATE
GRCITBPG	1824	RO	19	19	15000	12500	N	N	N	18AUG/8

REMARKS											

D/S HAS LENGTH	SPILLWAY TYPE	MAXIMUM DISCHARGE (FT.)	VOLUME OF DAM (CV)	POWER CAPACITY INSTALLED (KW)	PROCESSED NO.	NAVIGATION LOCKS
1	200 C	126	23700			

OWNER	ENGINEERING BY	CONSTRUCTION BY
NH WATER RESOURCES BOARD		

REGULATORY AGENCY		
DESIGN	CONSTRUCTION	OPERATION
NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE DAY MO YR	AUTHORITY FOR INSPECTION
ANDERSON-NICHOLS + COMPANY, INC.	19JUN78	P.L. 92-367

REMARKS	

END

FILMED

8-85

DTIC